Items.	*Per.*	*Quan*
Relieving weir—		
Earthwork	L. S. Rs	60
Burnt brick in surki mortar	C. ft.	2,6
Burnt stone slabs	S. ft.	1,01
Chunam plastering	Sqr.	8·5
Chunam pointing	,,	6·5
Concrete	C. ft.	40
Rough stone sujicut	C. yds.	62
Earthwork at flank	,,	200
Burnt stone, dry	,,	48
Cutting groves	L. S. Rs.	10
Teakwood shutter, complete	,,	40
Masonry drop at 1000th link—		
Excavation	L. S. Rs.	10
Brick in surki	C. ft.	226
Hammer dressed stone in chunam	,,	253
Burnt stone slabs	S. ft.	98
Chunam plastering	Sqr.	1·00
Chunam pointing	,,	1·00
Concrete	C. ft.	22
Channel proper—		
Hard soil	C. yds.	9,595
Soft rock	,,	803
Mile stone	Each.	1
Index stones	,,	14
Bed grade stones	,,	15

V. ARUNACHALA MUDALIAR, *Offg Exec. Engr.*

CHITALDRUG DIVISION.

The 8th March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 15th of April 1899, for constructing a new tank at Parasurampur Challakere taluk. An approximate estimate of quantities is given below. These quantities are no guaranteed. The work should be completed by the end of June 1902 A. D.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's offic at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executiv Engineer. The tenders should be accompanied by a statement, in the form given below, showing he rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 (five hundred only) in cash o Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank at Parasurampur, Challakere taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	*Unit of work.*	*Rate per unit.*
Bund—		
Digging seat of bund	C. yds.	10,444
Clearing silt (halla)	,,	21,413
Earthwork to bund (gravelly soil)	,,	39,376
Black cotton soil mixed with gravel	,,	86,504
Earthwork from kodi cutting	,,	4,127
Black cotton mixed with gravel to be carted from a distance (breached).	,,	107,635
Turfing	S. yds.	36 348
Grade stones	No.	64
New stone work	C. yds.	17,530
Top width stone	No.	64
Bench mark stone	,,	2
Date stone	,,	1
Gauge stone	,,	1
Tank No. stone	,,	1
Baling water by engine, halla by deep and springs powerful.	L. S.	

Description of work.	*Unit of work.*	*Rate per unit.*
r—		
Earthwork excavation	C. yds.	4,127
Burnt brick in chunam	C. ft.	1,377
Burnt stone slabs	S. ft.	239
Burnt stone in chunam	C. ft.	1,725
Plastering with chunam	Sqr.	5·82
Blasting rock	C. yds.	203
Sluice No. 1		
Burnt brick in surki	C. ft.	4,135
Do archwork	,,	694
Burnt stone slabs	S. ft.	362
Do slabs dressed roughly	C. ft.	178
Plastering with surki	Sqr.	33·99
Cornice	R. ft.	46
Steel girders	L. S.	1
Lifting gear	L. S.	3
Plug with rod	L. S.	2
Shutter with rod	L. S.	1
Concrete	C. ft.	1,406
Bridge	L. S.	1
Sluice No. 2 *as per No.* 1.		
hannels—		
Earthwork excavation	C. yds.	21,550
Mile and zero stones	No.	11
Half furlong stones	,,	143
Bed grade stones	,,	152
elieving weirs—		
Earthwork (excavation)	C. yds.	662
Brick in chunam	C. ft.	2,915
Plastering with chunam	S. yds.	3·60
Rough stone work	C. yds.	580
Burnt stone slabs	S. ft.	1,274
rt Bridges—		
Earthwork (excavation)	C. yds.	12
Burnt stone slabs	S. ft.	728
Cut stone work	C. ft.	284
Plastering with chunam	Sqr.	4·87
Gravel	C. yds.	25
Burnt stone in chunam	C. ft.	199
Irrigation sluices	No.	14
Aqueduct (the design and details to be entered after knowing the nature of stream, &c.)	Lump. sum.	
Quarters for stores	Do	

K. PRAHLADA RAO,
Executive Engineer.

FRENCH ROCKS DIVISION.

The 20th March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 15th April 1899, for constructing the Executive Engineer's quarters at French Rocks.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 11-30 A.M. to 4-30 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing Executive Engineer's Quarters at French Rocks," in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.